

AD-A156 109

NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
CHESHAM POND DAM (NH.) (U) CORPS OF ENGINEERS WALTHAM MA
NEW ENGLAND DIV MAR 80

1/1


UNCLASSIFIED

F/G 13/13

NL

END

Find MEU



MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

AD-A156 109

CONNECTICUT RIVER BASIN
HARRISVILLE, NEW HAMPSHIRE

CHESHAM POND DAM
NH 00063

STATE NO 109.02

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM



DTIC
ELECTE
JUL 08 1985
S D
G

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154

DTIC FILE COPY

MARCH 1980

DISTRIBUTION STATEMENT A
Approved for public release
Distribution Unlimited

85 06 13 058

DISCLAIMER NOTICE

**THIS DOCUMENT IS BEST QUALITY
PRACTICABLE. THE COPY FURNISHED
TO DTIC CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO NOT
REPRODUCE LEGIBLY.**

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NH 00063	2. GOVT ACCESSION NO. AD-A156 109	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Chesham Pond Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE March 1980
		13. NUMBER OF PAGES 40
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		16a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Connecticut River Basin Harrisville, New Hampshire Minnewawa Brook		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The dam is a concrete gravity dam and earthen embankment 125 ft. long and 16 ft. high. The dam is in fair condition. It is small in size with a significant hazard classification. A breach in the dam could cause potential for loss of 1-2 lives and appreciable property damage. There are various major concerns which must be corrected to assure the continued performance of the dam.		



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
424 TRAPELO ROAD
WALTHAM, MASSACHUSETTS 02154

REPLY TO
ATTENTION OF:
NEDED

JUN 19 1980

Honorable Hugh J. Gallen
Governor of the State of New Hampshire
State House
Concord, New Hampshire 03301

Dear Governor Gallen:

Inclosed is a copy of the Chesham Pond Dam Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Water Resources Board, the cooperating agency for the State of New Hampshire. In addition, a copy of the report has also been furnished the owner, the State of New Hampshire.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Water Resources Board for your cooperation in carrying out this program.

Sincerely,


MAX B. SCHEIDER

Colonel, Corps of Engineers
Division Engineer

Incl
As stated

NATIONAL DAM INSPECTION PROGRAM
PHASE I INSPECTION REPORT

Identification No.: NH00063
Name of Dam: Chesham Pond Dam
Town: Harrisville
County and State: Cheshire County, New Hampshire
Stream: Minnewawa Brook
Date of Inspection: September 13, 1979

BRIEF ASSESSMENT

Chesham Pond Dam is a concrete gravity dam and earthen embankment 125 feet in length with a hydraulic height of 16 feet. The spillway consists of a concrete ogee spillway 41 feet in length. A concrete sluiceway structure is adjacent to the northwest end of the spillway and contains a gate-operated low-level outlet 2'H x 3.5'W. The gate is operated by a hand operated mechanism located directly above the gate. A highway crossing is located just downstream of the dam. Stone masonry training walls are located on either side of the spillway discharge channel and terminate against the highway embankment. The dam spans Minnewawa Brook and is located in southwest New Hampshire. The drainage area above the dam is 8.2 square miles and contains Silver Lake, Childs Bog, and Seaver Reservoirs. Maximum storage capacity is approximately 630 acre-feet. Normal pool is approximately 0.55 miles in length with a surface area of 70 acres. Chesham Pond is currently used for recreational purposes.

The dam is in fair condition. Major concerns are: inadequate spillway capacity, deterioration of the mortar in the stone masonry training walls on both sides of the discharge channel between the dam and the highway embankment, lack of vegetation and erosion resistance on the upstream slope of the embankment section near the southeast end of the dam, and trees growing on the upstream and downstream slopes of the dam.

The dam is of small size and significant hazard classification based on storage volume and potential for loss of 1-2 lives and appreciable property damage in event of a breach. In accordance with the Recommended Guidelines for Safety Inspection of Dams, the test flood may range from the 100-year to $\frac{1}{2}$ the Probable Maximum Flood (PMF). A test flood equal to $\frac{1}{2}$ PMF was selected because of the potential for loss of 1-2 lives in the event of a breach. To determine the test flood outflow, the Seaver Reservoir Dam Phase I Inspection Report was consulted. The drainage area to Seaver Dam is 4.4 square miles and the resulting test flood outflow ($\frac{1}{2}$ PMF) was determined to be 2,660 cfs. The subdrainage area to Chesham Pond Dam is 3.8 square miles of steeply sloping terrain (166 ft/mile). Using the PMF Peak Flow Rates graph, the peak discharge for a 'mountainous' watershed, having a drainage area of 3.8 square miles, was determined to be 8,740 cfs. Therefore, the test flood inflow from the subdrainage area would be 4,370 cfs. Using the $\frac{1}{2}$ PMF discharge from Seaver Reservoir Dam of 2,660 cfs and the test flood inflow from the subdrainage area of 4,370 cfs, the total test flood inflow to Chesham

Pond Dam was determined to be approximately 7,000 cfs (854 csm). It should be noted that the peaks for the test flood outflow from Seaver Reservoir Dam and the inflow from the subdrainage area would probably not occur at the same time. However, for the purposes of this Phase I investigation, the test flood inflow will be assumed to equal the summation of these two values. Using the procedure outlined in Estimating Effect of Surcharge Storage on Maximum Probable Discharges issued by the Corps, to determine the modifying effect of surcharge storage on the test flood inflow, the routed test flood outflow was determined to be 6,000 cfs (732 csm) at elevation 1161.2' NGVD. The test flood analysis indicates that the dam would be overtopped by 4.8 feet during the test flood. Maximum spillway capacity at top of dam is 535 cfs which is 9 percent of the routed test flood outflow.

The owner, the New Hampshire Water Resources Board, should implement the results of the recommendations and remedial measures given in Sections 7.2 and 7.3 within one year after receipt of this Phase I Inspection Report.

Warren A. Guinan

Warren A. Guinan
Project Manager
N.H. P.E. 2339

DTIC
ELECTE
S JUL 08 1985 D
G

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A/1	23 CW

This Phase I Inspection Report on Chesham Pond Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.

Richard J. Di Bruno

RICHARD DIBUONO, MEMBER
Water Control Branch
Engineering Division

Aramast Mahtesian

ARAMAST MAHTESIAN, MEMBER
Foundation & Materials Branch
Engineering Division

Carney M. Terzian

CARNEY M. TERZIAN, CHAIRMAN
Design Branch
Engineering Division

APPROVAL RECOMMENDED:

Joe B. Fryar

JOE B. FRYAR
Chief, Engineering Division

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

TABLE OF CONTENTS

Title	Page
LETTER OF TRANSMITTAL.....	
BRIEF ASSESSMENT.....	
REVIEW BOARD PAGE.....	
PREFACE.....	v
TABLE OF CONTENTS.....	vi
OVERVIEW PHOTO.....	vii
LOCATION MAP.....	viii

REPORT

SECTION

1	PROJECT INFORMATION.....	1-1
	1.1 General.....	1-1
	1.2 Description of Project.....	1-1
	1.3 Pertinent Data.....	1-3
2	ENGINEERING DATA.....	2-1
	2.1 Design.....	2-1
	2.2 Construction.....	2-1
	2.3 Operation.....	2-1
	2.4 Evaluation.....	2-1
3	VISUAL INSPECTION.....	3-1
	3.1 Findings.....	3-1
	3.2 Evaluation.....	3-2
4	OPERATIONAL PROCEDURES.....	4-1
	4.1 Procedures.....	4-1
	4.2 Maintenance of Dam.....	4-1
	4.3 Maintenance of Operating Facilities.....	4-1
	4.4 Description of Any Warning System in Effect.....	4-1
	4.5 Evaluation.....	4-1
5	HYDROLOGY AND HYDRAULIC ANALYSIS.....	5-1
	5.1 Evaluation of Features.....	5-1
6	STRUCTURAL STABILITY.....	6-1
	6.1 Evaluation of Structural Stability.....	6-1
7	ASSESSMENT, RECOMMENDATIONS & REMEDIAL MEASURES.....	7-1
	7.1 Dam Assessment.....	7-1
	7.2 Recommendations.....	7-1
	7.3 Remedial Measures.....	7-2
	7.4 Alternatives.....	7-2

APPENDICES

Designation

VISUAL INSPECTION CHECK LISTS.....	A
ENGINEERING DATA.....	B
PHOTOGRAPHS.....	C
HYDROLOGY AND HYDRAULIC COMPUTATIONS.....	D
INFORMATION AS CONTAINED IN THE NATIONAL INVENTORY OF DAMS.....	E




Figure 1 - Overview of Chesham Pond Dam. June 1979



Reprinted by permission of the Department of Resources and Economic Development, Concord, N.H. 03301, and the copyright owners, The National Survey, Chester, VT. 0-17-78.

SCALE IN MILES



MAP BASED ON STATE OF NEW HAMPSHIRE
OFFICIAL HIGHWAY MAP.

Anderson-Nichols & Co., Inc.		U.S. ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASS.	
CONCORD	NEW HAMPSHIRE		
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
CHESHAM POND DAM LOCATION MAP			
MINNEWAWA BROOK		NEW HAMPSHIRE	
		SCALE: SEE BAR SCALE	
		DATE: MARCH 1980	

NATIONAL DAM INSPECTION PROGRAM
PHASE I INSPECTION REPORT
CHESHAM POND DAM

SECTION 1
PROJECT INFORMATION

1.1 General

a. Authority. Public Law 92-367, August 8, 1972 authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Anderson-Nichols & Company, Inc. has been retained by the New England Division to inspect and report on selected dams in the State of New Hampshire. Authorization and notice to proceed were issued to Anderson-Nichols under a letter of March 22, 1979 from John P. Chandler, Colonel, Corps of Engineers. Contract No. DACW33-79-C-0050, as changed, has been assigned by the Corps of Engineers for this work.

b. Purpose

(1) To perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.

(2) To encourage and prepare the States to initiate quickly effective dam safety programs for non-Federal dams.

(3) To update, verify and complete the National Inventory of Dams.

1.2 Description of Project

a. Location. Chesham Pond Dam is located in the Town of Harrisville, New Hampshire and impounds a reservoir of small size. Chesham Dam is the downstream dam in a series of four dams which impound the headwaters of Minnewawa Brook. After discharging at damsite, Minnewawa Brook flows southwesterly approximately 7 miles to its confluence with Otter Brook to form The Branch. The Branch then continues another 2.5 miles to Keene, New Hampshire where it joins the Ashuelot River. The Ashuelot River is a major tributary in the Connecticut River Basin. Chesham Pond Dam is shown on U.S.G.S. Quadrangle, Monadnock, New Hampshire with coordinates approximately at N42°56'15", W72°08'23", Cheshire County, New Hampshire. (See Location Map page viii.)

b. Description of Dam and Appurtenance. Chesham Pond dam is a concrete gravity dam and earthen embankment 125 feet in length with a hydraulic height of 16 feet. Beginning at the southeast end of the dam and going northwest the dam consists

APPENDIX A
VISUAL INSPECTION CHECKLIST

(5) Inspect the spillway when no water is flowing over it for evidence of leakage or undermining.

The owner should carry out the recommendations made by the engineer.

.3 Remedial Measures

a. Operating and Maintenance Procedures. The owner should:

(1) Clear trees for a distance of 25 feet on either side of the discharge channel between the dam and the highway that crosses the channel downstream of the dam.

(2) Remove trees from the shore of the pond for a distance of 100 feet upstream from the intake to the low-level outlet at the east end of the dam.

(3) Repair the spalled concrete at the southeast abutment all.

(4) Visually inspect the dam and appurtenant structures once a month.

(5) Engage a professional engineer qualified in the design and construction of dams to make a comprehensive technical inspection of the dam once every year.

(6) Establish a surveillance program for use during and immediately after heavy rainfall and also a downstream warning program to follow in case of emergency conditions.

(7) Establish trespassing control.

(8) Ensure operation of low-level outlet.

.4 Alternatives

One.

SECTION 7
ASSESSMENT, RECOMMENDATIONS, AND REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition. The visual examination indicates that Chesham Pond Dam is in fair condition. The major concerns with respect to the integrity of the dam are:

- (1) Inadequate spillway capacity.
- (2) Deterioration of the mortar in the stone masonry training walls on both sides of the discharge channel between the dam and the highway embankment which crosses the channel downstream of the dam.
- (3) Lack of vegetation and erosion resistance on the upstream slope of the embankment section near the southeast end of the dam.
- (4) Trees growing on the upstream and downstream slopes of the dam.

b. Adequacy of Information. The information from the visual inspection and hydraulic analyses is adequate to identify the problems listed in 7.2. These problems will require the attention of a professional engineer who will have to make additional engineering studies to design or specify remedial measures. No additional information is needed for the purposes of this Phase I investigation.

c. Urgency. The owner should implement the recommendations in 7.2 and 7.3 within one year after receipt of this Phase I report.

7.2 Recommendations

The owner should retain a professional engineer qualified in the design and construction of dams to:

- (1) Perform a more detailed investigation to evaluate spillway adequacy and overtopping potential.
- (2) Specify procedures for repair of the stone masonry training walls on both sides of the discharge channel between the dam and the highway embankment that crosses the channel downstream of the dam.
- (3) Specify procedures for providing adequate erosion resistance on the upstream slope of the embankment section of the dam.
- (4) Specify and oversee procedures for removing trees and their root systems from the embankment section of the dam. Also specify and oversee the filling of the voids remaining from the root system removal.

SECTION 6 STRUCTURAL STABILITY

6.1 Visual Observations

The visual examination indicates the following potential structural problems:

(1) Deterioration of the mortar in the stone masonry training walls on both sides of the discharge channel between the dam and the highway embankment which crosses the channel downstream of the dam.

(2) Lack of vegetation and erosion resistance on the upstream slope of the embankment section near the southeast end of the dam.

(3) Trees growing on the upstream and downstream slopes of the embankment section which could cause seepage or erosion problems if a tree blows over and pulls out its roots or if a tree dies or is cut and its roots rot.

6.2 Design and Construction Data

In a letter dated June 30, 1949, it is stated that the contractor who built the original dam in 1921 stated "that most of this dam is built of very large boulders... (and) the bottom of this dam was planked and there was some decay there."

6.3 Post-Construction Changes

A letter dated April 20, 1949 states that the dam "appears to be in a weak state and is in need of immediate repairs or reconstruction." A petition for repair dated September 6, 1949 states that the reconstruction will consist of "cement" {sic!}.

6.4 Seismic Stability

This dam is located in Seismic Zone 2 and, in accordance with the Phase I guidelines, does not warrant seismic analysis.

by the Corps, to determine the modifying effect of surcharge storage on the test flood inflow, the routed test flood outflow was determined to be 6,000 cfs (732 csm) at elevation 1161.2' NGVD. The test flood analysis indicates the dam would be overtopped by 4.8 feet during the test flood. Maximum spillway capacity at top of dam is 535 cfs which is 9 percent of the routed test flood outflow.

f. Dam Failure Analysis. The impact of failure of the dam with pool level at top of dam was assessed. Because of the tandem relationship of Childs Bog, Seaver and Chesham Dams, the three dams were analyzed through the use of the Corps of Engineers HEC-1DB computer program. With this analysis, it could be determined how much overtopping would occur at each dam under various breach conditions. Since Chesham Pond Dam is the most downstream, the analysis of all these results is not necessary to determine the appropriate hazard classification for Chesham. Therefore, only the breach of Chesham will be discussed in this report.

A breach of Chesham Pond Dam was analyzed from the dam to a point about 1 mile downstream. The breach was assumed to occur at the top of dam and develop to the toe of the dam. The time for a breach to develop with a bottom width of 50 feet and side-slopes 1H:1V was estimated to be one hour. A breach of this magnitude resulted in a discharge of 6,960 cfs. One trailer located about 200 feet downstream of the dam could be inundated by 3.2 feet of water. This could cause damage to the structure and possibly cause loss of 1-2 lives. The road crossing, one-half mile downstream of the dam, could be overtopped by about 5.1 feet of water with a breach discharge of 6,470 cfs. Damage to the roadway and culvert could occur. Two houses located about 8 and 10 feet above streambed, just upstream from the road crossing, could be subjected to property damage. (See Appendix C - Figure 12.) The next road crossing, one mile downstream of the dam, could be overtopped by 3 feet with a breach discharge of 5,500 cfs. (See Appendix C - Figure 13.) This amount of overtopping could possibly damage the gravel roadway and culvert. The reach between these two road crossings provides a large storage area for attenuation of the breach wave. (See Appendix C - Figure 14.) One house in this reach, located about ten feet above the streambed, may be subjected to basement flooding.

A breach of Chesham Pond Dam could result in the possible loss of 1-2 lives and cause appreciable property damage. Based on this analysis, Chesham Pond Dam was classified Significant Hazard.

SECTION 5
HYDROLOGIC/HYDRAULIC

5.1 Evaluation of Features

a. General. Chesham Pond Dam is a concrete gravity dam which impounds a reservoir of small size. The drainage area to the damsite consists of 8.2 square miles of moderately to steeply sloping terrain. Silver Lake, Childs Bog, and Seaver Reservoir are storage areas in the upstream watershed. The total length of the dam is 125 feet with a hydraulic height of 16 feet. The concrete ogee spillway is 41 feet in length. A low-level outlet structure is located in the northwest abutment. A roadway is located immediately downstream of the dam. Discharge from the dam passes through the roadway in a corrugated metal pipe arch with a span of 14' 11" and rise of 10' 2".

b. Design Data. No design data were disclosed.

c. Experience Data. According to a letter dated October 13, 1938, Chesham Pond Dam had a flow of about 4 feet over the spillway crest during the flood of September 21-24, 1938. No other experience data was found.

d. Visual Observations. At the time of inspection, no visual evidence was noted of damage to any portions of the dam caused by excessive discharges.

e. Test Flood Analysis. Chesham Pond Dam is classified as being small in size, having a hydraulic height of 16 feet and a maximum storage capacity of 630 acre-feet. The dam was determined to have a significant hazard classification. Using the Recommended Guidelines for Safety Inspection of Dams, the test flood may range from the 100-year to $\frac{1}{2}$ the Probable Maximum Flood (PMF). A test flood equal to $\frac{1}{2}$ PMF was selected because of the potential for loss of 1-2 lives in the event of a breach. To determine the test flood inflow, the Seaver Reservoir Dam Phase I Inspection Report was consulted. The drainage area to Seaver Dam is 4.4 square miles and the resulting test flood outflow ($\frac{1}{2}$ PMF) was determined to be 2,660 cfs. The subdrainage area to Chesham Pond Dam is 3.8 square miles of steeply sloping terrain (166 ft/mile). Using the PMF Peak Flow Rates graph, the peak discharge for a 'mountainous' watershed, having a drainage area of 3.8 square miles, was determined to be 8,640 cfs. Therefore, the test flood inflow from the subdrainage area would be 4,370 cfs. Using the $\frac{1}{2}$ PMF discharge from Seaver Reservoir Dam of 2,660 cfs and the test flood inflow from subdrainage area of 4,370 cfs, the total test flood inflow to Chesham Pond Dam was determined to be approximately 7,000 cfs (854 csm.) Using the procedure outlined in Estimating Effect of Surcharge Storage on Maximum Probable Discharges issued

SECTION 4 OPERATIONAL PROCEDURES

4.1 Procedures

Chesham Pond Dam is owned and operated by the New Hampshire Water Resources Board (NHWRB). The normal recreational lake level is maintained at the permanent spillway crest during the summer season. The lake level is lowered in the fall by use of the low-level outlet to provide storage for spring runoff and to enable property owners to make shoreline improvements.

4.2 Maintenance of Dam

NHWRB is responsible for the maintenance of the dam.

4.3 Maintenance of Operating Facilities

Throughout the year, the dam is visited on a weekly basis by a maintenance staff member of the NHWRB. A weekly log is kept on conditions at the dam site. The gate was not operated during the inspection; however, the mechanism appeared to be in satisfactory condition but has surface rust.

4.4 Description of Any Warning System in Effect

No written warning system was disclosed.

4.5 Evaluation

The current operation and maintenance procedures, consisting of a weekly program of inspection, should ensure that all minor problems encountered can be remedied within a reasonable period of time.

Some trees have grown on the upstream slope of the embankment section near the abutment and also on the downstream slope near the training wall on the east side of the channel. (See Appendix C - Figure 6.) No seepage was observed on the downstream embankment section of the dam.

c. Appurtenant Structures. The concrete low-level outlet structure at the northwest end of the spillway is approximately 4.5' wide and supports the sluice gate operating mechanism and wooden racks. (See Appendix C - Figure 7.) The concrete was observed to be in good condition with only a minor hair line crack in the concrete wall at one corner and only minor surface erosion of the concrete at the water line. The wooden decking over the sluice way channel was observed to be in good condition with only minor evidence of weathering and warping. The gate operating mechanism, which is a hand operated racket type, was observed to be in fair condition with some surface rust. (See Appendix C - Figure 8.) There was no indication of recent lubrication or operation. The trash racks which have been constructed of 2x4 wood members, were observed to be weathered.

d. Reservoir. The watershed above the reservoir is moderately to steeply sloping and heavily wooded. (See Appendix C - Figure 9.) The slopes of the reservoir appear stable. No evidence of significant sedimentation was observed. There are some trees overhanging the edge of the pond immediately upstream from the intake to the low-level outlet.

e. Downstream Channel. A roadway is located 20 feet downstream of the dam. (See Appendix C - Figure 10.) The channel downstream of the culvert is tree lined on both banks. (See Appendix C - Figure 11.)

3.2 Evaluation

On the basis of the results of the visual inspection, Chesham Pond Dam is considered to be in fair condition.

Deterioration of the mortar between the stone blocks in the stone masonry training walls on both sides of the discharge channel between the dam and highway immediately downstream could lead to failure of the walls and subsequent failure of the soil abutments of the dam.

The lack of vegetation on the upstream slope of the embankment section near the east end of the dam has led to some erosion, if allowed to continue, could result in breaching of the dam.

Trees growing on the upstream and downstream slopes of the embankment section of the dam could cause seepage or erosion problems if a tree blows over and pulls out its roots or if a tree dies or is cut and its roots rot.

SECTION 3
VISUAL INSPECTION

3.1 Findings

a. General. Chesham Pond Dam is a low dam which impounds a reservoir of small size. The watershed above the reservoir is moderately to steeply sloping and heavily wooded. The downstream area is moderately sloping. From the southeast end of the concrete gravity section to the southeast abutment (which is not clearly defined) there is an embankment section about 65 feet long.

b. Dam. Chesham Pond Dam is a concrete gravity dam with a hydraulic height of 16 feet and totaling 125 feet in length. (See Appendix C-Figures 2 and 3.) The downstream face of the spillway is inclined at 1H:1V.

Both abutments of the dam consist of soil. There are many large boulders at the downstream toe of the dam, but no evidence near the dam of anything that appears to be bedrock. No information was found in the available records as to whether the dam is founded on bedrock or soil. Therefore, it is not possible to conclude what material the dam is founded on.

Water was flowing over the dam at the time of the inspection. As a result it is not possible to determine whether any leakage is taking place under the dam.

Stone masonry training walls are located on either side of the discharge channel between the dam and the roadway culvert about 20 feet downstream. The mortar between the stone blocks in these training walls is badly deteriorated. No water was leaking through these walls above tailwater except for one leak at an elevation 0.6 foot below pond level where the training wall on the east side of the channel meets the stone masonry wall which retains the highway fill. (See Appendix C-Figure 4.) It is considered unlikely that this leakage is coming from the pond.

The concrete weir was observed to be in good condition with minor surface erosion of the concrete at the water line. The training wall (abutment) at the southeast end of the weir was eroded and spalled up to 2" deep. (See Appendix C-Figure 5.)

The upstream slope of the embankment section has very little vegetation near the southeast end of the dam (apparently this is due to trespassing) and has experienced some erosion.

SECTION 2 ENGINEERING DATA

2.1 Design

No original design plans were found for Chesham Pond Dam. Plans for repairs in 1949 were found in the files of the New Hampshire Water Resources Board (NHWRB).

2.2 Construction Records

No construction records were revealed.

2.3 Operation

No engineering operational data were found.

2.4 Evaluation

a. Availability. A search of the files of the NHWRB revealed the plans of repairs in 1949 and other general historical information which was utilized in the preparation of this report.

b. Adequacy. The information obtained from the files of the NHWRB was used in conjunction with the visual inspection and the hydrologic and hydraulic computations to make the final assessments and recommendations of this investigation.

c. Validity. The structure as seen on the visual inspection is in close conformity to the disclosed plans and information.

(7) Impervious core - unknown

(8) Cutoff - unknown

(9) Grout curtain - unknown

h. Diversion and Regulating Tunnel - not applicable
(See j. below.)

i. Spillway

(1) Type - concrete gravity ogee spillway with a sloping downstream face (1H:1V).

(2) Length of weir - 41'

(3) Crest elevation - 1154' NGVD (See 1.3 c (6) above)

(4) Gates - none

(5) U/S Channel - Numerous cottages and homes are located around the reservoir. The reservoir slopes are wooded. No significant sedimentation at the damsite was observed.

(6) D/S Channel - About 20 feet downstream from the spillway apron is a roadway crossing. Discharge over the spillway passes through the roadway in a corrugated metal pipe arch with a span of 14' 11" and rise of 10' 2".

j. Regulating Outlets. There is one 2.0'H x 3.5'W low-level opening located in the sluiceway structure adjacent to the northwest end of the spillway. This opening is controlled by a CI sluice gate. The invert of the opening is at elevation 1146.6' NGVD.

(6) Spillway crest - 1154 (Shown on USGS Quadrangle Sheet and assumed to be spillway crest elevation.)

(7) Original design surcharge - unknown

(8) Top of dam - 1156.4

(9) Test flood pool - 1161.2

d. Reservoir Length (miles)

(1) Maximum pool - 0.57

(2) Spillway crest pool - 0.55

(3) Flood control pool - not applicable

e. Storage (acre-feet)

(1) Recreation pool - 460

(2) Flood control pool - not applicable

(3) Spillway crest pool - 460

(4) Top of dam - 630

(5) Test flood pool - 1140

f. Reservoir Surface Area (acres)

(1) Recreation pool - 70

(2) Flood control pool - not applicable

(3) Spillway crest - 70

(4) Test flood pool - 115

(5) Top of dam - 84

g. Dam

(1) Type- concrete gravity dam with earth embankment

(2) Length - 125'

(3) Height - 16' (structural and hydraulic)

(4) Topwidth - varied

(5) Side slopes - varied

(6) Zoning - unknown

The lake level is lowered in the fall by use of the low-level outlet. Throughout the year, the dam is visited on a weekly basis by a maintenance staff member of the NHWRB. A weekly log is kept on conditions at the damsite.

1.3 Pertinent Data

a. Drainage Area. The drainage area consists of 8.2 square miles (5,248 acres) of moderately to steeply sloping terrain. Silver Lake, Childs Bog and Seaver Reservoir are located in the upstream watershed. The normal pool of Chesham Pond has a surface area of 70 acres which constitutes 1 percent of the watershed.

b. Discharge at Damsite

(1) Outlet works - one 2.0'H x 3.5'W low-level opening controlled by CI sluice gate at invert elevation 1146.6' NGVD. Approximate capacity at top of dam - 120 cfs at 1156.4' NGVD.

(2) The maximum discharge at the damsite is unknown. However, a flow of 48 inches over spillway crest was reported during the flood of September 21-24, 1938. If this depth of flow over the spillway were to occur today, the approximate discharge would be 1,270 cfs with 1.6 feet of overtopping.

(3) Ungated spillway capacity at top of dam - 535 cfs @ 1156.4' NGVD

(4) Ungated spillway capacity at test flood elevation - 2,770 cfs @ 1161.2' NGVD

(5) Gated spillway capacity at top of dam - not applicable

(6) Gated spillway capacity at test flood elevation - not applicable

(7) Total spillway capacity at test flood elevation - 2,770 cfs @ 1161.2' NGVD

(8) Total project discharge at test flood elevation - 6,000 cfs @ 1161.2' NGVD

c. Elevation (ft. above NGVD of 1929; formerly called Mean Sea Level (MSL); see (6) below).

(1) Streambed at centerline of dam - 1140.8 (downstream invert pipe arch)

(2) Maximum tailwater - unknown

(3) Upstream gate invert - 1146.6

(4) Recreation pool - 1154

(5) Full flood control pool - not applicable

of the following sections: an earthen embankment 65 feet in length, a concrete spillway abutment, a concrete ogee spillway 41 feet long, and a concrete low-level sluiceway. The sluiceway structure contains a gate-operated mechanism located directly above the gate. The sluiceway intake is protected with a trash rack. A highway crossing is located just downstream of the dam. Discharge over the spillway passes through the roadway in a corrugated metal pipe arch with a span of 14'-11" and a rise of 10'2". Stone masonry training walls are located on either side of the spillway discharge channel and terminate against the highway embankment. The dam was originally constructed integrally with a railroad embankment long since abandoned, but the bridge seats remain in the downstream training walls mentioned above.

c. Size Classification. Small (hydraulic height-16 feet; storage-630 acre-feet) based on storage (≥ 50 to < 1000 acre-feet) as given in the Recommended Guidelines for Safety Inspection of Dams.

d. Hazard Classification. Significant hazard. A breach with pool at top of dam could result in the loss of 1-2 lives and cause appreciable property damage. For details see Section 5.1 f.

e. Ownership. Chesham Pond Dam was reported to have been built in 1921. The name of the original owner was not found. Ownership in 1930 was recorded to have been Breed Pond Company, in Marlborough, New Hampshire, formerly owned by Whitney. It is possible that Whitney was the original owner. Files from the New Hampshire Water Resources Board (NHWRB) indicate that the NHWRB took over ownership sometime between 1949 and 1968.

f. Operator. The current owner and operator of Chesham Pond Dam is the NHWRB. Mr. Vernon Knowlton, Chief Engineer, 37 Pleasant Street, Concord, New Hampshire 03301. Phone (603) 271-3406.

g. Purpose of Dam. The dam was previously used for storage purposes and is currently utilized for recreation.

h. Design and Construction History. According to the files at the NHWRB, the dam was originally built in 1921. No design or construction information was found regarding the original construction. The files also indicate the concrete spillway apron was constructed October 6, 1937. Plans of repairs made in 1949 were found. These plans were engineered and drawn by the Public Service Company of New Hampshire and dated August 9, 1949. Repairs included construction of the present sluiceway structure.

i. Normal Operating Procedures. The normal recreational level is maintained at the crest of the permanent spillway.

VISUAL INSPECTION CHECKLIST
PARTY ORGANIZATION

PROJECT CHESHAM POND DAM, N.H.

DATE September 13, 1979

TIME 9:30 AM

WEATHER Sunny, warm

W.S. ELEV.	U.S.	DN.S.
	<u>1154'</u>	<u>1142.1'</u>
	NGVD	NGVD

PARTY:

- | | |
|-----------------------------------|-----------|
| 1. <u>Warren Guinan (ANCo)</u> | 6. _____ |
| 2. <u>Stephen Gilman (ANCo)</u> | 7. _____ |
| 3. <u>David Deane (ANCo)</u> | 8. _____ |
| 4. <u>Ronald Hirschfeld (GEI)</u> | 9. _____ |
| 5. _____ | 10. _____ |

	PROJECT FEATURE	INSPECTED BY	REMARKS
1.	Hydrology/Hydraulics	D. Deane/W. Guinan	
2.	Structural Stability	S. Gilman	
3.	Soils and Geology	R. Hirschfeld	
4.	_____	_____	_____
5.	_____	_____	_____
6.	_____	_____	_____
7.	_____	_____	_____
8.	_____	_____	_____
9.	_____	_____	_____
10.	_____	_____	_____

PERIODIC INSPECTION CHECKLIST

PROJECT CHESHAM POND DAM, N.H. DATE Sept. 13, 1979

PROJECT FEATURE _____ NAME _____

DISCIPLINE _____ NAME _____

AREA EVALUATED	CONDITION
<u>DAM EMBANKMENT</u>	
Crest Elevation	
Current Pool Elevation	
Maximum Impoundment to Date	
Surface Cracks	None observed
Pavement Condition	Not paved
Movement or Settlement of Crest	None observed
Lateral Movement	None observed
Vertical Alignment	Good
Horizontal Alignment	Good
Condition at Abutment and at Concrete Structures	Trespassing and bare soil on upstream slope next to left end of spillway
Indications of Movement of Structural Items on Slopes	None observed
Trespassing on Slopes	See "Condition at Abutment..." above
Sloughing or Erosion of Slopes or Abutments	See "Condition at Abutment..." above
Rock Slope Protection - Riprap Failures	No riprap
Unusual Movement or Cracking at or Near Toe	None observed
Unusual Embankment or Downstream Seepage	None observed
Piping or Boils	None observed
Foundation Drainage Features	None observed
Toe Drains	None observed
Instrumentation System	None observed
Vegetation	Trees on upstream slope near left end of spillway

PERIODIC INSPECTION CHECKLIST

PROJECT CHESHAM POND DAM, N.H. DATE Sept. 13, 1979
 PROJECT FEATURE _____ NAME _____
 DISCIPLINE _____ NAME _____

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u>	
a. Approach Channel	
Slope Conditions	Not applicable
Bottom Conditions	Not visible beneath pond surface
Rock Slides or Falls	Not applicable
Log Boom	None
Debris	None
Condition of Concrete Lining	Not visible
Drains or Weep Holes	None
b. Intake Structure	
Condition of Concrete	Good; a little surface erosion of concrete at waterline
Stop Logs and Slots - Trashrack	Weathered wood

PERIODIC INSPECTION CHECKLIST

PROJECT CHESHAM POND DAM DATE Sept. 13, 1979

PROJECT FEATURE _____ NAME _____

DISCIPLINE _____ NAME _____

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - CONTROL TOWER</u>	
a. Concrete and Structural	
General Condition	Good
Condition of Joints	Good-one hairline crack at change in direction of wall
Spalling	Minor erosion of concrete at water surface
Visible Reinforcing	None
Rusting or Staining of Concrete	Only at embedded items
Any Seepage or Efflorescence	None visible
Joint Alignment	Not applicable
Unusual Seepage or Leaks in Gate Chamber	None visible
Cracks	See "condition of joints" above
Rusting or Corrosion of Steel	Railings are painted-good Other items are surface eroded
b. Mechanical and Electrical	
Gate Operating Mechanism	Hand operated ratchet type, good condition-surface rust only. No indication of recent operation.
	Note: Wood decking over control tower is treated wood planking in fair condition; some evidence of weathering and warping.

PERIODIC INSPECTION CHECKLIST

PROJECT CHESHAM POND DAM DATE SEPTEMBER 13, 1979

PROJECT FEATURE _____ NAME _____

DISCIPLINE _____ NAME _____

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u>	
a. Approach Channel	
General Condition	Good.
Loose Rock Overhanging Channel	None
Trees Overhanging Channel	Some trees at edge of pond immediately upstream of low-level outlet
Floor of Approach Channel	Not visible beneath pond surface
b. Weir and Training Walls	
General Condition of Concrete	Good
Rust or Staining	Only at embedded steel items
Spalling	Minor surface erosion of concrete of training walls at water surface. Left training wall-old concrete portion spalled and eroded.
Any Visible Reinforcing	None
Any Seepage or Efflorescence	None
Drain Holes	None
c. Discharge Channel	
General Condition	Fair
Loose Rock Overhanging Channel	None
Trees Overhanging Channel	Trees overhanging channel between spillway and roadway and downstream of roadway.
Floor of Channel	Boulders
Other Obstructions	Culvert under roadway immediately downstream of spillway

APPENDIX B
ENGINEERING DATA

BREED POND COMPANY

Marlboro N. H.
June 30 1949

State of New Hampshire
Water Resources Board
Concord, N. H.

Attention Mr. Walter G. White

Dear Mr. White:

Supplimenting our letter of June 3rd. we wish to say that we have contacted the Contractor who built this dam in 1921 and he has gone over it very carfully and states that most of this dam is built of very large boulders and could not possibly give way only on the top. The cause of the small leaks which were evident at the time of our last letter were in his estimation due to the fact that the bottom of this dam was planked and there was so me decay there.

This contractor is figuring out the best thing to do and will submit his report very soon.

In the mean time the water in this pond is down to a safe level due to the dry weather and the drawing from it for power purposes.

We will report more as soon as possible.

Very Truly yours,

Breed Pond Company



Robert C. Derby Clerk.

**NEW HAMPSHIRE WATER CONTROL COMMISSION
DATA ON RESERVOIRS & PONDS IN NEW HAMPSHIRE**

LOCATIONAT DAM NO. 109.02Town Harrisville: County CheshireStream Chesham PondBasin—Primary Connecticut: Secondary Minnewawa BrookLocal Name Symonds Reservoir**DRAINAGE AREA**Controlled Sq. Mi.: Uncontrolled Sq. Mi.: Total 8.15 Sq. Mi.**ELEVATION vs. WATER SURFACE AREA vs. VOLUME**

Point	Head Feet	Surface Area Acres	Volume Acre Ft.
(1) Max. Flood Height
(2) Top of Flashboards
(3) Permanent Crest
(4) Normal Drawdown	<u>8</u>	<u>74.20</u>
(5) Max. Drawdown
(6) Original Pond	<u>1154</u> U.S.G.S

Base Used: Coef. to change to U.S.G.S. Base

RESERVOIR CAPACITY


	Total Volume	Useable Volume
Drawdownft.ft.
Volumeac. ft.ac. ft.
Acre ft. per sq. mi.
Inches per sq. mi.

USE OF WATER StorageOWNER Breed Pond Reservoir Co. Harrisville N.H.


REMARKS Condition Good Wing Wall Badly Cracked

CHESHAM POND DAM - HARRIS, ILL.


109.02



PLAN



PROFILE



X-SECTION

B-3

NEW HAMPSHIRE WATER CONTROL COMMISSION
DATA ON DAMS IN NEW HAMPSHIRE

LOCATION STATE NO. 109.02
Town Harrisville : County Cheshire
Stream Chesham Pond
Basin-Primary Connecticut : Secondary Minnewawa Brook
Local Name Symonds Reservoir
Coordinates—Lat. 42° 55' + 3,600 : Long. 72° 10' - 9,600

GENERAL DATA

Drainage area: Controlled.....Sq. Mi.: Uncontrolled..... Sq. Mi.: Total 8.15 Sq. Mi.
Overall length of dam 86.....ft.: Date of Construction 1921
Height: Stream bed to highest elev. 13.....ft.: Max. Structure 10.75..... ft.
Cost—Dam : Reservoir

DESCRIPTION

Waste Gates

Type
Number 1 : Size 2.25 ft. high x 3.5 ft. wide
Elevation Invert 8 : Total Area 7.875 sq. ft.
Hoist

Waste Gates Conduit

Number : Materials
Size.....ft.: Length.....ft.: Area..... sq. ft.

Embankment

Type
Height—Max. ft.: Min. ft.
Top—Width : Elev. ft.
Slopes—Upstream on : Downstream on
Length—Right of Spillway : Left of Spillway

Spillway

Materials of Construction
Length—Total 46.5.....ft.: Net..... ft.
Height of permanent section—Max. 10.2 ft.: Min. 10.75 ft.
Flashboards—Type : Height 19 ft.
Elevation—Permanent Crest : Top of Flashboard
Flood Capacity 605 cfs.: 75 cfs/sq. mi.

Abutments

Materials:
Freeboard: Max. 2.25.....ft.: Min. ft.

Headworks to Power Devel.—(See "Data on Power Development")

OWNER Breed Pond Reservoir Co. Harrisville N.H.

REMARKS

Storage

Rec'd 10/15/38

Jacobson	
Holmgren	✓
<i>Edmund</i>	
Replied	
Filed	
10/15/38	

WATER CONTROL COMMISSION

STATE OF NEW HAMPSHIRE

Concord, New Hampshire

October 13, 1938.

Breed Pond Reservoir Co.,
Marlboro, N H

Known as Symonds Pond

RE: Chesham Pond Dam. W. C. C. No. 109.02

Gentlemen:

In order that we may determine the magnitude and extent of the flood of September 21-24 just passed, we are requesting the various dam owners in the State to supply us with the following information:

1. Was this dam injured? Ans. no
2. If so, to what extent? Ans. _____
3. Did all flashboards go out? Ans. _____
4. What was the maximum height of water over the permanent crest of spillway? Ans. Est. 48"
5. At what day and hour did the maximum flood height reach your dam? Ans. _____

6. Any other interesting information regarding the flood or rain fall may be given on the back of this sheet, or attach sheets.

Will you please return this letter with as much information as you can give us as promptly as possible. A self-addressed envelope is attached hereto.

We thank you for your cooperation.

Very truly yours,

Richard S. Holmgren

Richard S. Holmgren
Chief Engineer

CDC:GMB
Enc.

B-5

NEW HAMPSHIRE WATER RESOURCES BOARD

INVENTORY OF DAMS AND WATER POWER DEVELOPMENTS

DAM

BASIN Connecticut NO. 2 109.02
 RIVER Chasham Pond MILES FROM MOUTH D.A.SQ.MI 8.15
 TOWN Harrisville OWNER Bread Pond Reservoir Co.
 LOCAL NAME OF DAM _____
 BUILT 1911 DESCRIPTION Timber & Stone Concrete

POND AREA-ACRES 54.2023 DRAWDOWN FT. _____ POND CAPACITY-ACRE FT. _____
 HEIGHT-TOP TO BED OF STREAM-FT. 10-13 MAX. _____ MIN. _____
 OVERALL LENGTH OF DAM-FT. 50 MAX. FLOOD HEIGHT ABOVE CREST-FT. _____
 PERMANENT CREST ELEV. U.S.G.S. _____ LOCAL GAGE _____
 TAILWATER ELEV. U.S.G.S. _____ LOCAL GAGE _____
 PILLWAY LENGTHS-FT. 40 FREEBOARD-FT. 2.25/ft 21.10" ft.
 SLASHBOARDS-TYPE, HEIGHT ABOVE CREST 19"
 WASTE GATES-NO. WIDTH MAX. OPENING DEPTH SILL BELOW CREST
1 3.5 2.25 8

REMARKS Condition Good. Wing wall badly cracked. New concrete
into Munroe Park, Ashline Rd. 10/19/19 about 2' up
face + 15" thick at bottom downst.

POWER DEVELOPMENT

UNITS NO.	RATED HP	HEAD FEET	C.F.S. FULL GATE	KW	MAKE

SE 10/19/19

REMARKS Selectmen call this Symonds Reservoir.

DATE 1922 D.S.C.
12/7/37 H & J/L/S.

Table inspected


Harrisville

Inspected June 13, 1930.



Simmonds Pond, also known as Chesham Pond, owned by Breeds Pond Association formerly owned by Whitney.

Small concrete dam built in 1921 near railroad and highway. The main dam seemed dry and in good condition. There were some small cracks on the west wing wall just east of the gate outlet. The west wing wall was quite badly cracked about sixteen feet from the gage board. No serious results however, as the earth back of the wing walls is in quite good condition.

No picture.



SECTION B-B



PLAN

NOTE: ALL ELEVATIONS ARE BASED ON SPILLWAY CREST ASSUMED ELEVATION OF 1154 NGVD

ANDERSON-NEUMAN & CO., INC.
CONCORD, NEW HAMPSHIRE

U.S. ARMY ENGINEER DIVISION
CORPS OF ENGINEERS
WALTHAM, MA


CHESHAM POND DAM

NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS

DATE: 10/10/00

BY: NAD/00/0000


CHESTNUT POND - TOP OF DAILY WEIR SECTION



1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

- FREE OVERFLOW OGEE CREST
- CONTRACTED WINGWALL D/S ON EASTERLY SIDE
- PIPE ARCH BENEATH ROAD IMMEDIATELY D/S WILL CONTROL AT HIGH DISCHARGE

Plan of Spillway



Normal Pool = Spillway Crest = 1154 msl from quad
 $L = 41'$ Take $C = 3.5$ Top of Dam = 1156.4 (low point)

$$Q = CLH^{3/2} = (3.5)(41)H^{3/2} = 143.5 H^{3/2}$$

Dam Embankment - see attached sketch.

$$Q = CLH^{3/2} \quad L \text{ varies with } H \text{ take } C = 2.5$$

- Determine when (or if) pipe arch capacity controls
 Assume 31 concrete radius for pipe arch

NO. 3273-23 Chesham Pond Dam

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

Drainage Area = 8.2 square miles

Size Classification = Small

Hazard Classification = Significant

Test Flood Range = $\frac{1}{4}$ to $\frac{1}{2}$ PMFChosen Test Flood = $\frac{1}{2}$ PMF ; storage is in upper range of size classification and potential for loss of 4-6 lives.**STEP #1**

Calculate test flood using "Preliminary Guidance for Estimating Maximum Probable Discharges in Phase I Dam Safety Inspection, March, 1978"

 $\frac{1}{2}$ PMF discharge at Seaver Reservoir Dam, with a drainage area of 4.4 mi^2 , was determined to be 2,660 cfs. This value was obtained from the Seaver Reservoir Dam Phase I inspection report (NH00094).Apply guide curves to sub drainage area of 3.8 square miles. Find slope of sub DA. Length of longest watercourse 2.2 miles. Change in elevation $1520 - 1154 = 366 \text{ ft}$. Therefore, slope of watershed $\approx 166 \text{ ft/mi}$ - use 'mountainous' curve to obtain csm value of 2300.

$$3.8 \text{ mi}^2 \times 2300 \text{ csm} = 8,740 \text{ cfs (PMF Inflow)}$$

Test Flood equals $\frac{1}{2}$ PMF $\therefore 4,370 \text{ cfs}$

$$\begin{array}{r} \frac{1}{2} \text{ PMF Inflow to Chesham} = 2,660 \text{ cfs} \\ + 4,370 \text{ cfs} \\ \hline 7,030 \text{ cfs} \end{array}$$

Use 7,000 cfs as test flood inflow (Q_p)**STEP #2a.** Determine surcharge height to pass Q_p of 7,000 cfs. To do this a rating curve of Chesham Pond Dam must be calculated.



**NATIONAL PROGRAM OF INSPECTION OF
NON-FED. DAMS**

CHESHAM POND DAM
HARRISVILLE, NEW HAMPSHIRE

REGIONAL VICINITY MAP


MARCH 1980

DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

ANDERSON-NICHOLS & CO., INC.

CONCORD, NH


SCALE IN MILES



MAP BASED ON U.S.G.S. 7.5 MINUTE QUADRANGLE
SHEET. MONADNOCK, N.H. 1949.


APPENDIX D

HYDROLOGIC AND HYDRAULIC COMPUTATIONS




October 1979

Figure 14 - Overview of the reach between the two
road crossings shown in Figures 11 and
12 above.



October 1979
Figure 12 - Overview of the road crossing located
 $\frac{1}{2}$ mile downstream of the dam.




October 1979
Figure 13 - Overview of the road crossing located
one mile downstream of the dam.



September 13, 1979
Figure 10 - Looking downstream at pipe arch from
low-level outlet structure.



September 13, 1979
Figure 11 - View of the discharge channel downstream
of the pipe arch.



September 13, 1979
Figure 8 - Looking at the control mechanism for the
low-level gated outlet.



September 13, 1979
Figure 9 - Looking into the upstream reservoir from
the dam.



September 13, 1979
 Figure 6 - Looking southeasterly across the crest
 of the embankment.



September 13, 1979
 Figure 7 - View of downstream face of northwest end
 of spillway and low-level outlet structure.



September 13, 1979
 Figure 4 - Seepage at intersection of highway culvert headwall and training wall on southeast side of spillway discharge channel.



September 13, 1979
 Figure 5 - Close-up of spalled area on training wall at southeast abutment.




September 13, 1979
Figure 2 - Looking southeast across crest of the dam.



September 13, 1979
Figure 3 - Looking northwest across the crest of dam.

1



Anderson-Nichols & Co., Inc.		U.S. ARMY ENGINEER DIV. NEW ENGLAND	
CONCORD		CORPS OF ENGINEERS	
NEW HAMPSHIRE		WALTHAM, MA.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
PHOTO INDEX			
MINNEWAWA BROOK		NEW HAMPSHIRE	
		SCALE: NOT TO SCALE	
		DATE: MARCH 1980	

APPENDIX C
PHOTOGRAPHS

JOB NO. _____

SQUARES
1/4 IN. SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

Design of a 12" V.C. ChannelMinimum elevation 1156.4 $Q = 0$ - @ elev. 1156.7 $L = 25$ avg $H = .2$ $TKC = 2.5$

$$Q = CLH^{3/2} = (2.5)(25)(.2)^{3/2} = 6 \text{ cfs}$$

- @ elev. 1157.0 $L = 32$ avg $H = .4$ $Q = (2.5)(32)(.4)^{3/2} = 20$ - @ elev. 1157.2 $L = 40$ avg $H = .5$ $Q = (2.5)(40)(.5)^{3/2} = 35$ - @ elev. 1157.5 $L = 54$ avg $H = .7$ and $L = 45$ avg $H = .3$

$$Q = (2.5)(54)(.7)^{3/2} + (2.5)(45)(.3)^{3/2} = 98$$

- @ elev. 1158.0 $L = 60$ avg $H = .9$ and $L = 55$ avg $H = .7$ and $L = 24$ avg $H = .3$

$$Q = (2.5)(60)(.9)^{3/2} + (2.5)(55)(.7)^{3/2} + (2.5)(24)(.3)^{3/2} = 218$$

- @ elev. 1158.5 $L = 60$ avg $H = 1.1$ and $L = 30$ avg $H = .7$

$$Q = (2.5)(60)(1.1)^{3/2} + (2.5)(30)(.7)^{3/2} = 480$$

- @ elev. 1159.0 $L = 60$ avg $H = 1.5$ and $L = 72$ $H = 1.5$ and $L = 36$ avg $H = 1.0$

$$Q = (2.5)(60)(1.5)^{3/2} + (2.5)(72)(1.5)^{3/2} + (2.5)(36)(1.0)^{3/2} = 814$$

JOB NO.

SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
 4 IN. SCALE

- @ elev. 1159.5 $L = 60$ $H = 2.4$ and $L = 85$ $H = 1.9$
 and $L = 41$ $H = 1.2$

$$Q = (2.5)(60)(2.4)^{3/2} + (2.5)(85)(1.9)^{3/2} + (2.5)(41)(1.2)^{3/2} = 1249$$

- @ elev. 1166.0 $L = 60$ $H = 2.9$ and $L = 96$ $H = 2.2$
 and $L = 48$ $H = 1.6$

$$Q = (2.5)(60)(2.9)^{3/2} + (2.5)(96)(2.2)^{3/2} + (2.5)(48)(1.6)^{3/2} = 1767$$

- @ elev. 1161.0 $L = 60$ $H = 3.9$ and $L = 180$ $H = 2.5$
 and $L = 70$ $H = 2.2$

$$Q = (2.5)(60)(3.9)^{3/2} + (2.5)(180)(2.5)^{3/2} + (2.5)(70)(2.2)^{3/2} = 3505$$

- @ elev. 1162.0 $L = 60$ $H = 4.9$ and $L = 140$ $H = 2.8$
 and $L = 97$ $H = 2.7$

$$Q = (2.5)(60)(4.9)^{3/2} + (2.5)(140)(2.8)^{3/2} + (2.5)(97)(2.7)^{3/2} = 4343$$

- @ elev. 1163.2 $L = 60$ $H = 6.1$ and $L = 160$ $H = 3.5$
 and $L = 132$ $H = 3.5$

$$Q = (2.5)(60)(6.1)^{3/2} + (2.5)(160)(3.5)^{3/2} + (2.5)(132)(3.5)^{3/2} = 7040$$

@ elev. 1164.0 $L = 60$ $H = 6.9$ and $L = 190$ $H = 4.1$
 and $L = 155$ $H = 4.1$

$$Q = (2.5)(60)(6.9)^{3/2} + (2.5)(190)(4.1)^{3/2} + (2.5)(155)(4.1)^{3/2} = 9879$$

@ elev. 1165.0 $L = 60$ $H = 7.9$ and $L = 210$ $H = 4.8$
 and $L = 185$ $H = 4.8$

$$Q = (2.5)(60)(7.9)^{3/2} + (2.5)(210)(4.8)^{3/2} + (2.5)(185)(4.8)^{3/2} = 13715$$


JOB NO.

CHESAPEE PONDSQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
1/4 IN. SCALE

ELEVATION (FT)	SPILLWAY			SLUICeway		PIPE ARCH			DAM CREST	COMBINED
	L	H	Q	H	Q	Q	H	ELEV.	Q	Q
1154.0	41	0	0							0
1154.2	41	.2	13							13
1154.5	41	.5	51							51
1155.0	41	1.0	144							144
1155.7	41	1.7	318							318
1156.4	41	2.4	534						0	534
1156.7	40	2.7	621						4	627
1157.0	39	3.0	709						20	729
1157.2	39	3.2	781	0	0	781	7.3	1148.1	35	816
1157.5	38	3.5	871	.3	4	875	7.9	1148.7	98	873
1158.0	37	4.0	1036	.8	19	1055	8.9	1149.7	218	1273
1158.5	36	4.5	1203	1.3	39	1242	10.2	1151.0	480	1722
1159.0	35	5.0	1409	1.8	63	1472	11.3	1152.1	814	2286
1159.5	34	5.5	1535	2.3	91	1626	12.3	1153.1	1249	2875
1160.0	33	6.0	1697	2.8	123	1820	13.8	1154.6	1767	3587
1161.0	32	7.0	2074	3.8	194	2168	16.3	1157.1	3505	5673
1163.2*						2809	22.4	1163.2*	7040	9849
1164.0						3100	23.2	1164.0	9879	12979
1165.0						3300	24.2	1165.0	13715	17015

* PIPE ARCH CONTROLS AT AND ABOVE THIS ELEVATION

Using the above trials establish a discharge rating curve for the dam.



JOB NO. _____

SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
SCALE 1/4"

$$Q_{p1} = 7,000 \text{ cfs} \Rightarrow \text{elevation } 1161.6' \text{ MSL}$$

STEP #2b Determine the volume of surcharge in inches of runoff. To do this a storage vs elevation curve must be determined. (See pages _____).

$$Q_{p1} \Rightarrow 7,000 \text{ cfs} \Rightarrow 1161.6' \text{ MSL} \Rightarrow 1200 \text{ AC-FT}$$

$$\text{Normal Storage (spillway crest)} \Rightarrow 460 \text{ AC-FT}$$

$$740 \text{ AC-FT} \times \frac{1}{8.2 \text{ mi}^2} \times \frac{1 \text{ mi}^2}{640 \text{ AC}} \times \frac{12 \text{ in}}{\text{ft}} = 1.69'' \text{ runoff (STOR}_1\text{)}$$

STEP #2c

$$Q_{p2} = Q_{p1} \left(1 - \frac{\text{STOR}_1}{9.5}\right) = 7,000 \left(1 - \frac{1.69''}{9.5''}\right) = 5,750 \text{ cfs}$$

STEP #3a Determine surcharge height and STOR₂ to pass Q_{p2}

$$5,750 \text{ cfs} \Rightarrow 1161' \text{ MSL} \Rightarrow 1110 \text{ AC-FT}$$

$$650 \text{ AC-FT} \times \frac{1}{8.2 \text{ mi}^2} \times \frac{1 \text{ mi}^2}{640 \text{ AC}} \times \frac{12 \text{ in}}{\text{ft}} = 1.49'' \text{ runoff (STOR}_2\text{)}$$

STEP #3b Average STOR₁ & STOR₂ and determine Q_{p3}

$$\frac{1.69'' + 1.49''}{2} = 3.18 \div 2 = 1.59'' \text{ runoff} \approx 0.13'$$

$$0.13' \times \frac{1}{8.2 \text{ mi}^2} \times \frac{1 \text{ mi}^2}{640 \text{ AC}} = 682 \text{ AC-FT}$$

$$682 \text{ AC-FT} + 460 \text{ AC-FT} = 1142 \text{ AC-FT} \Rightarrow 1161.2' \text{ MSL}$$

$$1161.2' \text{ MSL} \Rightarrow 6,000 \text{ cfs} \Rightarrow \text{Routed test flood outflow}$$

Top of dam = 1156.4' MSL therefore dam will be overtopped by 4.8 feet during test flood. Maximum spillway capacity at top of dam is 535 cfs which is only 9 percent of the routed test flood outflow.

JOB NO.

RES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
I. SCALE

STORAGE - ELEVATION

- FROM KEENE GAS-ELECTRIC DATA

@ Normal Pool el. 1154 $A = 70 \text{ ac}$ $Vol = 20 \text{ mil/ft}^3$
 $= 460 \text{ ac-ft}$

- Total draw 14' - Take invert of dam @ 1140.0

- FROM PLANIMETER

@ contour 1160 $A = 105 \text{ ac}$.

$$\Delta S = \frac{105 + 70}{2} \times 6 = 525 \text{ ac ft}$$

$$\text{Total} = 525 + 460 = 985$$


Storage-Elevation Points

el.	Storage
1140	0
1154	460
1160	985

100-01-202 TO DIVISIONS PER INCH BUILT WAYS. 12 BY 10 DIVISIONS.

GRAPH PAPER

PRINTED IN U.S.A.



D-11

on: Nichols & Company, Inc.

Subject

BREACH ANALYSIS SCHEMATICS

Sheet No. _____ of _____

Date _____

Computed _____

Checked _____

JOB NO.

HEC-1
SUMMARY

SCHEMATICS

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30


CASE 5 CHESAM POND FAILS

STA A2

CHILDS BOG DAM

$Q_p = 183$

EL. = 1376.5




INITIAL WSEL
@ TOP OF DAM 1376.5

STA A4

INLET TO SEAWATER RESERVOIR

$Q_p = 176$

EL. = 1201.2



Min el. 1200

STA A6


SEAWATER RESERVOIR DAM

INITIAL WSEL @ TOP OF

DAM 1204.3

$Q_p = 790$

EL. = 1204.3




STA A8

INLET TO CHESAM POND

$Q_p = 790$

EL. = 1162.5



Min el. 1158


STA A10

CHESAM POND DAM

INITIAL WSEL @

TOP OF DAM 1156.4

$Q_b = 6963$




6 houses at or
below 1162.0

STA A11

$Q_p = 6466$

EL. = 1142.2




Min el. 1134

STA A12

$Q_p = 5508$

EL. = 1140.1



1 House @ 1140

Min el. 1130

1 House @ 1144
1 House @ 1142
1 TRAILER @ 1139
(located 200 ft. up
of dam)

1/2 MI.

D-12

ENCLOSURE WITH PATH PACKAGE (DEC-1)
DAN SAFETY VERSION JULY 1978

42 NEW HAMPSHIRE DASH NUMBERS 00096,

[illegible]

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
84

0 4V I

N	545.	525.	506.	488.	471.	454.	438.	423.	408.	394.
---	------	------	------	------	------	------	------	------	------	------

273.	260.	256.	248.	240.	233.	226.	222.	219.	216.
------	------	------	------	------	------	------	------	------	------

Year	1982	1979	1977	1974	1971	1969	1966	1964	1961	1959
...	182	179	177	174	171	169	166	164	161	159

N	134.	132.	130.	128.	126.	124.	122.	120.	118.	117.
---	------	------	------	------	------	------	------	------	------	------

	98.	97.	95.	94.	92.	91.	90.	88.	87.
--	-----	-----	-----	-----	-----	-----	-----	-----	-----

K1 ROUTE COMBINED HYDROGRAPH THROUGH CHESAPE POND

y1	1	-1156.9	-1
----	---	---------	----

Y4	1158.	1158.5	1159.	1159.5	1160.	1161.	1163.2	1164.	1165.
----	-------	--------	-------	--------	-------	-------	--------	-------	-------

Y5 1273.	1722.	2286.	2875.	3587.	5673.	984.9	12979.	17015.
----------	-------	-------	-------	-------	-------	-------	--------	--------

SE 1140. 1148. 1151. 1155. 1156.4 1157.2 1160. 1162.5 1163.2 1165.

1011'6.4

	(1)	(2)	(3)	(4)
IN 50.	0.	1140.	1.0	1156.4
IN 50.	0.	1140.	1.0	1170.

K1 ROUTE HYDROGRAPH DOWN MINNEAPOLIS BROOK FOR 1/2 MILE

1

y6		91	1179	1138	1002	1130
y7	550.	1155.	700.	1140.	880.	1134.
y8					1000.	1020.

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
84

1

	.03	.03	1130.	1145.	2500.	.0016
Y ₂	.07	.03				

Year	1977	1978	1979	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100
1977	1977	1978	1979	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100

WI ROUTE HYDROGRAPH ANOTHER 7000 FT DOWN PINEVALE ROCK

2

100

V1 1
V6 .1
V7 R50.
V7 1020.
K 99

.05
1120.
1000.
1075.
1100.
1100.
1150.
900.
1120.
7000.
1000.
1080.
1120.
990.
1075.
1010.
1075.

h/1

PLAN 1 STATION A13

RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
1.00	5168	1086.0	1.50

PLAN 2 STATION A13


RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
1.00	590	1078.6	1.92

NO. 3273-23 Chesham Pond Dam

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29

Evaluate capacity of box culvert located about 1/2 mile downstream of Chesham Dam.

Road width = 35'



Use the orifice equation to determine the capacity of the culvert at top of road.

$$Q = CA \sqrt{2gh}$$

$$Q = (0.8)(101.5) \sqrt{64.4 \times 3.2} = 1,165 \text{ cfs}$$

Breach Q through reach $\approx 6,470$ cfs. Therefore, the culvert will not carry the breach Q . Weir flow will occur over the road along with pressure flow through the culvert. Develop a rating curve for the weir cross section shown on Sheet 3. Use weir equation $Q = CLH^{3/2}$, where $c \approx 2.7$.

Stage (ft. above invert)

Discharge (cfs)

6.4 (top road)

$$Q_{\text{ORIFICE}} = 1,165$$

7.4

$$Q_{\text{ORIFICE}} = (0.8)(101.5) \sqrt{64.4 \times 4.2}$$

$$Q_{\text{ORIFICE}} = 1,335$$

$$Q_{\text{WEIR}} = 2.7(100)(1.0)^{3/2} +$$

$$2.7(10)(1.0)^{3/2}$$

$$= 297$$

$$Q_{\text{TOTAL}} = 1,632$$

2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

StageDischarge (cfs)

8.4

$$Q_{ORIFICE} = (0.8)(101.5)\sqrt{4.4 \times 5.2} = 1485$$

$$Q_{WEIR} = 2.7(100)(2.0)^{3/2} + 2.7(\frac{1}{2}16)(2.0)^{3/2} + 2.7(\frac{1}{2}20)(2.0)^{3/2}$$

$$= 901$$

$$Q_{TOTAL} = 2,386$$

9.4

$$Q_{ORIFICE} = (0.8)(101.5)\sqrt{4.4 \times 6.2} = 1,623$$

$$Q_{WEIR} = 2.7(100)(3.0)^{3/2} + 2.7(\frac{1}{2}25)(3.0)^{3/2} + 2.7(\frac{1}{2}30)(3.0)^{3/2} = 1,789$$

$$Q_{TOTAL} = 3,412$$

11.4

$$Q_{ORIFICE} = (0.8)(101.5)\sqrt{4.4 \times 8.2} = 1,866$$

$$Q_{WEIR} = 2.7(100)(5.0)^{3/2} + 2.7(\frac{1}{2}41)(5.0)^{3/2} + 2.7(\frac{1}{2}50)(5.0)^{3/2} = 4,392$$

$$Q_{TOTAL} = 6,258$$

12.4

$$Q_{ORIFICE} = (0.8)(101.5)\sqrt{4.4 \times 9.2} = 1,976$$

$$Q_{WEIR} = 2.7(100)(6.0)^{3/2} + 2.7(\frac{1}{2}50)(6.0)^{3/2} + 2.7(\frac{1}{2}60)(6.0)^{3/2} = 6,151$$


$$Q_{TOTAL} = 8,127$$

Using the above trials, establish a stage/discharge curve. (See Sheet 4.)

Breach $Q = 6,470$ cfs Stage = 11.5 feet


Antecedent $Q = 535$ cfs Stage = 4.2 feet

Increase due to breach would be 7.3 feet. This increase could cause property damage to two houses located on the right bank of the channel. Loss of life would probably not occur. Damage to roadway and the structure could occur. The road would be overtopped by about 5.1 feet of water. One trailer/shack located 200 feet d/s the dam could be inundated by 3.2 feet of water. Loss of 102 lives is possible. (See HEC-1 Summary Schematic)



FEET ABOVE TOP OF ROAD


61-D



Sheet 3/8
L. Williams
1/30

STATIONING IN FEET

Sheet 4/8
L. Williams
4/10/20



D-20


JOB NO.

 SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
 1 IN. SCALE

Evaluate capacity of box culvert located about one mile downstream of Chesham Pond Dam.

Road width = 18'

Gravel Road on left side



Use the orifice equation to determine the capacity of the culvert at top of road.

$$Q = CA \sqrt{2gh}$$

$$Q = (0.8)(101.5) \sqrt{64.4 \times 5.25} = 1493 \text{ cfs}$$

Breach Q through reach $\approx 5,500$ cfs. Therefore, culvert will not carry breach Q . Weir flow will occur over the road along with pressure flow through the culvert. Develop a rating curve for the weir cross section shown on Sheet 7.

Use weir equation $Q = CLH^{3/2}$ to rate flow over roadway. Assume 'c' is ≈ 2.7 .

Stage (ft. above invert)

Discharge (cfs)

0

0

10.5 (top of road)

$Q_{\text{ORIFICE}} = 1493$

11.5

$$Q_{\text{ORIFICE}} = (0.8)(101.5) \sqrt{64.4 \times 6.25} = 1629$$

$$Q_{\text{weir}} = 2.7(211)(1.0)^{3/2} + 2.7(\frac{1}{2}20)(1.0)^{3/2} + 2.7(\frac{1}{2}5)(1.0)^{3/2} = 603$$

$$Q_{\text{TOTAL}} = 2096 \text{ cfs}$$

D-21

JOB NO.

 AREAS 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
 IN. SCALE
Stage (ft. above invert)Discharge (cfs)

12.5

$$Q_{\text{ORIFICE}} = (0.8)(101.5)\sqrt{64.4 \times 7.25} = 1,755$$

$$Q_{\text{WEIR}} = 2.7(211)(2.0)^{3/2} + 2.7(241)(2.0)^{3/2} + 2.7(210)(2.0)^{3/2} = 1,806$$

$$Q_{\text{TOTAL}} = 3,561 \text{ cfs}$$

14.0

$$Q_{\text{ORIFICE}} = (0.8)(101.5)\sqrt{64.4 \times 8.75} = 1,928$$

$$Q_{\text{WEIR}} = 2.7(211)(3.5)^{3/2} + 2.7(275)(3.5)^{3/2} + 2.7(216)(3.5)^{3/2} = 4,535$$

$$Q_{\text{TOTAL}} = 6,463$$

Using the above trials, establish a stage/discharge relationship. See curve on sheet 8.

Breach $Q = 5,500$ cfs Stage = 13.5 feet


Antecedent $Q = 535$ cfs Stage = 5.2 feet

Increase due to breach would be = 8.3 feet. This would result in the gravel roadway being overtopped by 3 feet. One house located in this reach may suffer some property damage. Loss of life is unlikely. A large storage area exists in this reach; the wave would be attenuated in this area. The 2nd road crossing would act as a dam and would fill up this area. After overtopping of the roadway, the lessened breach discharge would continue downstream.

This analysis, in conjunction with the HEC-1 analysis, supports the appropriate hazard classification of Chesham as Significant. A breach could possibly result in the loss of 1-2 lives and could cause appreciable property damage.

Sheet 7/8
L. Williams
10/80


CHESHAM POND DAM
WEIR SECTION - 2ND d/s culvert - D/s HAZARD ANALYSIS



D-23

Sheet 8/8
L. Williams
4/10/30.

CHESHAM POND DAM
RATING CURVE - 2ND d/s culvert - D/S HAZARD ANALYSIS



D-24

APPENDIX E

INFORMATION AS
CONTAINED IN THE NATIONAL
INVENTORY OF DAMS

NOT AVAILABLE AT THIS TIME

END

FILMED

8-85

DTIC